BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work: Earthwork and other Works for Temporary Immersion Tank for Lord Ganesh Idols at Thindlu Vidyaranyapura Main Road near BWSSB Overhead Tank in Ward No. 9, Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	42.00	Earth work in surface excavation in **hard soil** for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	219.42	
2	214.50	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in **Hard soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	283.02	
	214.50	Above 1.5 Mtrs Depth Add 25% Extra		353.78	
3	820.00	Code 0516 - Providing Plastic Sheet etc complete as per specifications and directions of engineer in charge of the work	Sqm	6.00	
4	150.00	Supply of water Through water Tank for filling Tank etc complete as per specifications and directions of engineer in charge of the work	Each	350.00	
5	12.50	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component etc complete as per specifications and directions of engineer in charge of the work	Cum	750.00	
6	60.00	Hire charge of pumping water 3.5 KL/hr capacity Pump etc complete as per specifications and directions of engineer in charge of the work	Hrs	50.00	
7	150	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc complete as per specifications and directions of engineer in charge of the work	Days	244.55	
8	3050.00	Hire Charges for Two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 0.50 mtrs C/C Horizontaly with Necessary earth work and labour etc complete as per specifications and directions of engineer in charge of the work	Rft	17.00	
9	12000.00	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc complete as per specifications and directions of engineer in charge of the work	Sft	3.00	

10	500.00	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc complete as per specifications and directions of engineer in charge of the work	Rft	17.00	
11	500	Hire Charge for Armless Plastic Chairs etc complete as per specifications and directions of engineer in charge of the work	Nos	4.00	
12	100	Hire Charge for Wooden Table of Size 6ft x 2ft etc complete as per specifications and directions of engineer in charge of the work	Nos	40.00	
13	1600.00	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathe daluminium wire etc complete as per specifications and directions of engineer in charge of the work	Mtrs	9.00	
14	80	Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc complete as per specifications and directions of engineer in charge of the work	Hrs	562.00	
15	130.00	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc complete as per specifications and directions of engineer in charge of the work	Nos	285.00	
16	5	Hire charges compoment name 1087 Crane charges etc complete as per specifications and directions of engineer in charge of the work	Day	4000.00	
17	357.50	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work	Cum	77.76	

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್ ನ
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ ಎ...(3ನೇ)
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿರಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore - 92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
21/12/11